



BRANZ Appraised

Appraisal No. 633 [2024]

INSULATED FAÇADE SYSTEM

Appraisal No. 633 [2024]

This Appraisal replaces BRANZ Appraisal No. 633 [2018]

Amended 10 June 2026



BRANZ Appraisals

Technical Assessments of products for building and construction.

Resene
Construction Systems

Rockcote Resene Ltd T/A Resene Construction Systems

PO Box 39 108
Harewood
Christchurch
Tel: 03 338 6328

Web: www.reseneconstruction.co.nz



BRANZ

1222 Moonshine Rd,
RDI, Porirua 5381
Private Bag 50 908
Porirua 5240,
New Zealand
Tel: 04 237 1170
branz.co.nz



Product

- 1.1 Insulated Façade System is a cavity-based Exterior Insulation and Finishing System (EIFS) wall cladding. It is an external wall cladding system for residential and light commercial type buildings where domestic construction techniques are used.
- 1.2 The system consists of Graphex (Neopor®), expanded polystyrene (EPS), extruded polystyrene (XPS) or polyisocyanurate (PIR) sheets fixed over battens to form the cavity. The plaster coating system consists of 5 mm thickness of fibreglass mesh reinforced, polymer-modified, cement-based plaster, which is finished with a cement-based finishing plaster that is then painted with a 100% acrylic-based paint system. The chosen finishing plaster is applied to give a range of different appearances, such as a sponge, patterned, adobe or spray textured finish. The system incorporates Resene Construction Systems EdgeSeal joinery flashings.

Scope

- 2.1 Insulated Façade System has been appraised as an external wall cladding system for buildings within the following scope:
 - the scope limitations of NZBC Acceptable Solution E2/AS1 for timber-framed buildings; and,
 - with a risk score of 0-20, calculated in accordance with NZBC Acceptable Solution E2/AS1; and,
 - situated in NZS 3604 Wind Zones up to, and including, Extra High.
- 2.2 Insulated Façade System has also been appraised for weathertightness and structural wind loading when used as an external wall cladding system for buildings within the following scope:
 - the scope limitations of NZBC Acceptable Solution E2/AS1; and,
 - constructed with timber and steel framing subject to specific engineering design; and,
 - situated in specific design wind pressures up to a maximum design differential ultimate limit state (ULS) of 2.5 kPa.
- 2.3 Insulated Façade System must only be installed on vertical surfaces (except for tops of parapets, sills and balustrades, which must have a minimum 10° slope and be waterproofed in accordance with the Technical Literature).
- 2.4 Insulated Façade System must only be used with window and doors that comply with NZBC Acceptable Solution E2/AS1 or that are covered by a valid BRANZ Appraisal or NZ CodeMark Certification.
- 2.5 Installation of components and accessories supplied by Resene Construction Systems and its approved installers must be carried out only by Resene Construction Systems approved installers.

Building Regulations

New Zealand Building Code (NZBC)

3.1 In the opinion of BRANZ, Insulated Façade System, if designed, used, installed and maintained in accordance with the statements and conditions of this Appraisal, will meet or contribute to meeting the following provisions of the NZBC:

Clause B1 STRUCTURE: Performance B1.3.1, B1.3.2 and B1.3.4. Insulated Façade System meets the requirements for loads arising from self-weight, wind, impact and creep [i.e. B1.3.3 (a), (h), (j) and (q)]. See Paragraphs 10.1-10.4.

Clause B2 DURABILITY: Performance B2.3.1 (b) 15 years, B2.3.1 (c) 5 years and B2.3.2. Insulated Façade System meets these requirements. See Paragraphs 11.1-11.3.

Clause E2 EXTERNAL MOISTURE: Performance E2.3.2. Insulated Façade System meets this requirement. See Paragraphs 16.1-16.5.

Clause F2 HAZARDOUS BUILDING MATERIALS: Performance F2.3.1. Insulated Façade System meets this requirement.

Technical Specification

4.1 System components and accessories for the Insulated Façade System supplied by Resene Construction Systems are as follows:

Cavity Battens

- **Graphex peel 'n' stick battens** – manufactured to meet the requirements of AS 1366.3 with an approximate density of 18 kg/m³. The battens are 45 mm wide by 21 mm thick, are supplied in 1,200 mm lengths and are coated on the back face with an acrylic adhesive, which is protected prior to installation by a removable film.
- **Standard EPS cavity battens** – manufactured from high density (Class H) EPS with an approximate density of 24 kg/m³. The battens are 40 mm wide by 22 mm thick and are supplied in 2,400 mm lengths.
- **Timber cavity battens** – nominal 50 mm wide by 25 mm thick (minimum finished size of 45 mm wide by 18 mm thick) timber treated to minimum Hazard Class H3.1.

Graphex

- **Graphex sheets** are 50-100 mm thick with an approximate density of 18 kg/m³. The sheets are supplied in lengths ranging from 2.4-3.6 m by 1.2 m wide and are manufactured to meet the requirements of AS 1366.3.

EPS Sheets

- **EPS sheets** are 40-100 mm thick Class H with an approximate density of 24 kg/m³, or 50 or 60 mm minimum thickness if using Class S with an approximate density of 16 kg/m³. The sheets are supplied in lengths ranging from 2.4-3.6 m by 1.2 m wide and are manufactured to meet the requirements of AS 1366.3.

XPS Sheets (XTherm Blue)

- **XPS sheets** are 50 mm thick with an approximate density of 34 kg/m³. The sheets are supplied in lengths ranging from 1.2-2.2 m by 0.6 m wide and are manufactured to meet the requirements of AS 1366.4.

PIR Sheets (XTherm Gold)

- **PIR sheets** are 50-100 mm thick with an approximate density of 35 kg/m³. The sheets are supplied in 2.4 m lengths by 1.2 m wide and are manufactured to meet the requirements of AS 1366.2.

Base, Levelling and Waterproofing Plasters

- A base [mesh] coat is applied using one of the following renders, followed by a subsequent coat of the same render to level the surface.
- **Coarse Mesh Render** is a polymer-modified, portland cement-based plaster supplied in 20 kg bags and mixed on site with clean drinking water. It is applied as the base coat in a minimum 2 mm layer followed by the embedment of fibreglass mesh reinforcement in the outer surface.
- **Rockcote PM100 Quick Render** is a dry mix, cement-based, polymer-modified plaster supplied in 20 kg bags and mixed on-site with clean water. It is used as a base coat for bonding and bedding the fibreglass mesh and is trowel-applied to an approximate thickness of 4-5 mm.
- **Resene Construction Systems RMaxx** is a high-yielding, cement-free dispersion based base coat plaster supplied in 20 kg pails. It is applied as the base coat in a minimum 1.5 mm layer followed by the embedment of fibreglass mesh reinforcement in the outer surface. An additional 1-1.5 mm is applied to fully encase the mesh.
- **HydroPlast** is an acrylic dry powder with cement activator, that when mixed with water creates a flexible waterproofing render for use over plastered balustrade and fixing blocks. It is supplied in 10 kg bags and is applied over the levelling render with a trowel in a 1 mm layer followed by the embedment of fibreglass mesh reinforcement in the outer surface.

Primer

- **Rockcote Render Prime** is a water-borne acrylic, polymer dispersion, tintable coating supplied in 15 L pails. It is brush or roller-applied as a primer between the selected base coat and acrylic texture.
- **Resene Limelock** is a water-borne acrylic, polymer dispersion, tintable coating supplied in 10 L pails. It is brush or roller applied as a primer between the mineral textures and the finishing system.

Mineral Texture Coating

- **Resene Construction Systems Mineral Texture Coatings** are dry mix, cement-based, polymer-modified plasters, supplied in 20 kg bags and mixed on site with clean water. They are trowel or spray applied to an approximate thickness of 1-3 mm.

Acrylic Texture Coating

- **Resene Construction Systems Acrylic Texture Coatings** are ready mixed, tintable, mineral-filled, polymer-based, elastomeric high-build coating with in pail and dry film preservatives, supplied in 15 L pails. They are spray or trowel applied to an approximate thickness of 0.5-2 mm. The selected Resene Construction Systems texture colour must have a minimum light reflectance value [LRV] of 25%.

uPVC Primer, Plaster Modifier, Waterproofing Plaster and Finishes

- **Multistop bedding compound** is used as a uPVC primer when mixed with diluted Acrylbond resin or water.
- **Acrylbond** is a water-based co-polymer resin supplied in 4 and 15 L pails used as a plaster modifier.
- **Resene Lumbersider** is a water-borne 100% acrylic-based protective finish for use over mineral and acrylic textures. It is supplied in 4 and 10 L pails and is brush or roller applied. The protective finish coat must have a minimum LRV of 25%.
- **Resene X200** is an acrylic waterproofing membrane for use as a protective finish over mineral and acrylic textures. It is supplied in 4 and 10 L pails and is brush, roller or spray applied. The protective finish coat must have a minimum LRV of 25%.

Accessories

- **Reinforcing mesh** - alkali-resistant fibreglass mesh with a nominal mesh size of approximately 5 x 4 mm square and a weight of 160 g/m² for use in domestic and light commercial situations.
 - **uPVC components** - starter strip flashing, standard corner flashing, vertical control joint, horizontal control joint, EdgeSeal sill, jamb and head flashings, and 40, 50, 60 mm and universal ventilated starter strips.
 - **3M All Weather Flashing Tape 8067** - flexible flashing tape with a proprietary backing and an acrylic pressure sensitive adhesive to seal the EdgeSeal head flashing to the building underlay. The tape is available 76 mm wide in rolls 22.8 m long.
 - **Sticky Mesh** - alkali-resistant fibreglass, 150 mm wide corner pieces.
 - **Graphex/EPS/XPS/PIR sheet nail fixings [timber frame]** - hot-dip galvanised steel flat head nails with 40 mm diameter washers. Refer to Table 1 for fixing length requirements.
 - **Graphex/EPS/XPS/PIR sheet screw fixings [timber frame]** - 8 g AS 3566 Corrosion Class 4 hot-dip galvanised wood screws with 40 mm diameter washers in NZS 3604 defined exposure zones B, C and D. Refer to Table 2 for fixing length requirements.
 - **Graphex/EPS/XPS/PIR sheet screw fixings [steel frame]** - 8 g self-drilling AS 3566 Corrosion Class 4 hot-dip galvanised screws with 40 mm diameter washers in NZS 3604 defined exposure zones B, C and D. Refer to Table 3 for fixing length requirements.
- [Note: Hot-dip galvanising must comply with AS/NZS 4680.]*
- **Washers** - 40 mm diameter polypropylene washers.

Table 1: Graphex/EPS/XPS/PIR sheet fixing lengths [nails to timber frame]

Sheet Thickness	Nail Size [mm]
40	90 x 3.55
50	100 x 3.75
60	110 x 4.0
70	125 x 5.3
80	150 x 6.0
90	150 x 6.0
100	150 x 6.0

Table 2: Graphex/EPS/XPS/PIR sheet fixing lengths [screws to timber frame]

Sheet Thickness	Minimum Screw Length [mm]
40	80
50	100
60	110
70	120
80	130
90	140
100	150

Table 3: Graphex/EPS/XPS/PIR sheet fixing lengths [screw to steel frame]

Sheet Thickness	Minimum Screw Length [mm]
40	80
50	95
60	95
70	105
80	115
90	125
100	135

- 4.2 Accessories specific to the system, which are supplied by the Resene Construction Systems approved applicator are:
- **Waterproof membrane tapes** - tapes covered by a valid BRANZ Appraisal for use as waterproofing membranes over tops of plastered parapets, balustrades, fixing blocks and the like.
- 4.3 Accessories used with the Integra Lightweight Concrete Façade System to a generic specification in accordance NZBC Acceptable Solution E2/AS1 or covered by a relevant and valid BRANZ Appraisal or NZ CodeMark Certification, which are supplied by the building contractor, are:
- Flexible wall underlay
 - Flexible wall underlay restraint
 - Rigid wall underlay
 - Flexible flashing tape
 - Thermal break [steel framing]
 - Flexible air seals
 - Sill support bars
 - Window head flashing
 - Flashings
 - Sealant

Handling and Storage

- 5.1 Handling and storage of all materials supplied by Resene Construction Systems, whether on-site or off-site, is under the control of the approved applicator and shall be handled according to the requirements in the Technical Literature. Graphex/EPS/XPS/PIR sheets, battens, uPVC flashings and profiles must be protected from direct sunlight and physical damage, and should be stored flat and under cover. Liquid components must be stored in frost-free conditions.
- 5.2 Handling and storage of all materials supplied by the building contractor, whether on-site or off-site, are under the control of the building contractor. Materials must be handled and stored in accordance with the relevant manufacturer's instructions.

Technical Literature

- 6.1 This Appraisal must be read in conjunction with:
- EPS Insulated Facade System - 50 mm EPS over Timber Frame - RMaxx RenderSpec, dated August 2024.
 - EPS Insulated Facade System - 50 mm EPS over Timber Frame - Acrylic RenderSpec, dated August 2024.
 - EPS Insulated Facade System - 50 mm EPS over Timber Frame - Mineral RenderSpec, dated August 2024.
 - Insulated Facade System, EPS Panel 50 mm [20 mm Cavity] standard details:
 - Foundation, Sheet 71.02.00, dated 1 November 2017.
 - External Corner, Sheet 71.03.00, dated 1 November 2017.
 - Internal Corner, Sheet 71.04.00, dated 1 November 2017.
 - Window Sill, Sheet 71.05.00, dated 4 November 2020.
 - Window Jamb, Sheet 71.06.00, dated 4 November 2020.
 - Window Head - Option 1, Sheet 71.07.00, dated 4 November 2020.
 - Soffit, Sheet 71.08.00, dated 1 November 2017.
 - Roof Apron, Sheet 71.09.00, dated 1 November 2017.
 - Vertical Control Joint - Option 1, Sheet 71.10.00, dated 1 November 2017.
 - Horizontal Control Joint, Sheet 71.11.00, dated 1 November 2017.

- 6.2 BRANZ has assessed the set of core weathertightness and installation details and specifications listed above. Resene Construction Systems has an extensive library of CAD details and specifications for various combinations of foam type and thicknesses, cavity depth and plaster finishes. The designer must select the correct details for their building design and confirm their suitability. Contact Resene Construction Systems for assistance.
- 6.3 All aspects of design, use, installation and maintenance contained in the Technical Literature and within the scope of this Appraisal must be followed.

Design Information

Framing

Timber Treatment

- 7.1 Timber framing must be treated as required by NZBC Acceptable Solution B2/AS1.

Timber Framing

- 7.2 Timber framing must comply with NZS 3604 for buildings or parts of buildings within the scope limitations of NZS 3604. Buildings or parts of buildings outside the scope of NZS 3604 must be to a specific design in accordance with NZS 3603 and AS/NZS 1170. Where specific design is required, the framing must be of at least equivalent stiffness to the framing provisions of NZS 3604. In all cases, studs must be at maximum 600 mm centres for buildings designed to NZS 3604 in Wind Zones up to, and including, Very High and at maximum 400 mm centres for buildings situated in NZS 3604 Wind Zone Extra High and specifically designed buildings situated in Wind Zones above NZS 3604 defined Extra High. Dwargs must be fitted flush between the studs at maximum 800 mm centres.
- 7.3 Timber framing must have a maximum moisture content of 24% at the time of the cladding application. *[Note: If sheets are fixed to framing with a moisture content of greater than 24%, problems may occur at a later date due to excessive timber shrinkage.]*

Steel Framing

- 7.4 Steel framing must be to a specific design meeting the requirements of the NZBC.
- 7.5 The minimum framing specification is 'C' section studs and nogs of overall section size of 75 mm web and 32 mm flange. Steel thickness must be minimum 0.55 mm.
- 7.6 For steel-framed buildings situated within NZS 3604 defined Wind Zones up to, and including, Very High, studs must be at maximum 600 mm centres. For all other buildings, studs must be at maximum 400 mm centres. Dwargs must be fitted flush between the studs at maximum 800 mm centres.

Graphex/EPS/XPS/PIR Sheet Setout

- 7.7 All vertical sheet edges must be supported and fixed through the cavity battens to the framing. Horizontal sheet edges must be supported at fixing locations with cavity spacers 100 mm maximum, in accordance with the requirements of NZBC Acceptable Solution E2/AS1. At the base of the wall, the sheets must hang 50 mm below the supporting framing.
- 7.8 Additional framing will be required at soffits, internal and external corners and window and door openings for the support and fixing of sheet edges.

General

- 8.1 When the Insulated Façade System is used for specifically designed buildings up to 2.5 kPa design differential ULS wind pressure, only the weathertightness aspects of the cladding and maximum framing centres and sheet fixing centres are within the scope of this Appraisal. All other aspects of the building need to be specifically designed and are outside the scope of this Appraisal.
- 8.2 Ground clearance to finished floor levels as set out in NZS 3604 must always be adhered to.
- 8.3 The horizontal separation between the wall cladding and the adjacent ground must be maintained in accordance with NZS 3604.

- 8.4 The bottom of cladding must have separations, clearances and overlaps in accordance with NZBC Acceptable Solution E2/AS1.
- 8.5 All external walls shall have barriers to airflow in accordance with NZBC Acceptable Solution E2/AS1 and for specifically designed buildings up to a 2.5 kPa design differential ULS wind pressure a rigid underlay is required. Where rigid underlays are used, the fixing lengths must be increased by a minimum of the thickness of the underlay.
- 8.6 Penetrations through the Insulated Façade System shall be in accordance with NZBC Acceptable Solution E2/AS1 and the Technical Literature.
- 8.7 Where the system abuts other cladding systems, designers must detail the junction to meet their own requirements and the performance requirements of the NZBC. The Technical Literature provides some guidance. Details not included within the Technical Literature have not been assessed and are outside the scope of this Appraisal.

Electrical Cables

- 8.8 PVC sheathed electrical cables must be prevented from direct contact with the sheets. When cables must penetrate the sheets for exterior electrical connections, the cable must be directly supported by passing through an electrical conduit.

Control Joints

- 8.9 Control joints must be constructed in accordance with the Technical Literature and be provided as follows:
- **Horizontal control joints** – at maximum 7 m centres and at inter-storey junctions in accordance with NZBC Acceptable Solution E2/AS1.
 - **Vertical control joints** – at maximum 8 m centres; aligned with any control joint in the structural framing, or where the system abuts different cladding types.

[Note: Horizontal and vertical control joints must be located to ensure the panel is adequately supported on both sides of the control joint. The Technical Literature provides some guidance for the design of vertical control joints where the system abuts different cladding types. Details not included within the Technical Literature are outside the scope of this Appraisal and are the responsibility of the designer – refer to Paragraph 8.7].

Structure

Mass

- 9.1 The mass of the Insulated Façade System is approximately 7 kg/m², therefore it is considered a light wall cladding in terms of NZS 3604.

Impact Resistance

- 9.2 The system has adequate resistance to hard body impacts likely to be encountered in normal residential use. Where a greater level of impact protection is required, a heavier grade of reinforcing mesh may be used. The heavy-grade fibreglass reinforcing mesh [360 g/m²] embedded in 5 mm thick plaster provides approximately four times the hard body impact strength of the standard grade mesh in 3 mm thick plaster. The likelihood of impact damage to the system when used in light commercial situations should be considered at the design stage, and appropriate protection such as the installation of bollards and barriers should be considered for vulnerable areas.

Wind Zones

- 9.3 Insulated Façade System is suitable for use in all Wind Zones of NZS 3604 up to, and including, Extra High where buildings are designed to meet the requirements of NZBC Acceptable Solution E2/AS1, Paragraph 1.1, or up to 2.5 kPa design differential ULS wind pressure where buildings are specifically designed.

Graphex/EPS/XPS/PIR Sheet Fixing

9.4 Sheets must be fixed through the cavity battens and cavity spacers to the wall framing at maximum centres specified in Table 4.

Table 4: Sheet Fixing Centres for Edges and Body of the Sheet

Maximum Fixing Centres [mm] in Relevant NZS 3604 Wind Zone						
Stud Centres	Low ¹	Medium ¹	High ¹	Very High ²	Extra High ³	SED up to 2.5 kPa ³
400 mm	300	300	300	200	150	150
600 mm	300	300	300	250	-	-

1. One fixing is also required into each dwang and top and bottom plates at mid length.
2. Fixings are also required to each dwang at 300 mm centres and top and bottom plates at mid-dwang length.
3. Fixings are also required at 300 mm centres along top and bottom plates.

Durability

10.1 Insulated Façade System meets the performance requirements of NZBC Clause B2.3.1 (b) 15 years for the cavity system and plaster finish, and the performance requirements of NZBC Clause B2.3.1 (c) 5 years for the exterior paint system.

Serviceable Life

- 10.2 Insulated Façade System is expected to have a serviceable life of at least 30 years, provided the system is maintained in accordance with this Appraisal, and the sheets, fixings and plaster are continuously protected by a weathertight coating and remain dry in service.
- 10.3 Microclimatic conditions, including geothermal hot spots, industrial contamination and corrosive atmospheres, and contamination from agricultural chemicals or fertilisers can convert mildly corrosive atmosphere into aggressive environments for fasteners. The fixing of sheets in areas subject to microclimatic conditions requires specific design in accordance with NZS 3604, and is outside the scope of this Appraisal.

Maintenance

- 11.1 Regular maintenance is essential to ensure the performance requirements of the NZBC are continually met and to ensure the maximum serviceability of the system.
- 11.2 Regular cleaning (at least annually) of the paint coating is required to remove grime, dirt and organic growth and to maximise the life and appearance of the coating. Grime may be removed by brushing with a soft brush, warm water and detergent. Paint systems must be re-coated at approximately 8-10 yearly intervals in accordance with the paint manufacturer's instructions.
- 11.3 Annual inspections must be made to ensure that all aspects of the cladding system, including the coating system, plaster, flashings and any sealed joints remain in a weatherproof condition. Any cracks, damaged areas or areas showing signs of deterioration which would allow water ingress, must be repaired immediately. Sealant, coatings and the like must be repaired in accordance with the instructions of Resene Construction Systems.
- 11.4 Minimum ground clearances as set out in this Appraisal and the Technical Literature must be maintained at all times during the life of the system. *[Note: Failing to adhere to the minimum ground clearances given in this Appraisal and the Technical Literature will adversely affect the long term durability of the Insulated Façade System.]*

Prevention of Fire Occurring

12.1 Separation or protection must be provided to Insulated Façade System from heat sources such as fireplaces, heating appliances and chimneys. NZBC Acceptable Solutions C/AS1 and C/AS2 provide methods for separation and protection of combustible materials from heat sources.

Control of Internal Fire and Smoke Spread

- 13.1 The Insulated Façade System includes Graphex/EPS/XPS/PIR sheets, which are combustible insulants. When used in ceilings or walls, the insulation including any surface lining product enclosing the insulation from the adjacent occupied space, must achieve the Group Number for internal surface finish requirements as specified in NZBC Acceptable Solutions C/AS1 or C/AS2.

Control of External Fire Spread

- 14.1 Refer to NZBC Acceptable Solutions C/AS1 and C/AS2 and NZBC Verification Method C/VM2 for fire resistance rating and control of external fire spread requirements for external walls.

Vertical Fire Spread

- 14.2 This Appraisal only covers buildings 10 m or less in height. NZBC Functional Requirement C3.2 identifies that external vertical fire spread to upper floors only needs be considered for buildings with a building height greater than 10 m. Control of external vertical fire spread is therefore outside the scope of this Appraisal.

Horizontal Fire Spread

- 14.3 Where the external wall is not protected by a sprinkler system or separated from the relevant boundary as required by NZBC Acceptable Solutions C/AS1 or C/AS2, the cladding system will need to be installed over a Fire Resistance Rated (FRR) external wall with the required FRR.

External Cladding Systems

- 14.4 Insulated Façade System comprising Graphex or XTherm Gold (PIR) sheets, mineral base coat with mineral texture finish, Resene Limelock, and Resene Lumbersider or X200 painted finish achieves a Type A classification when tested to ISO 5660.1 in accordance with the requirements of the NZBC Building Product Specifications.
- 14.5 Insulated Façade System comprising EPS sheet, mineral base coat with mineral texture finish, Resene Limelock, and Resene Lumbersider or X200 painted finish coat achieves a Type B classification when tested to ISO 5660.1 in accordance with the requirements of the NZBC Building Product Specifications.
- 14.6 The Graphex/EPS/XPS/PIR sheets used in the Insulated Façade System have been tested and comply with the flame propagation criteria of AS 1366 as required by NZBC Acceptable Solutions C/AS1 and C/AS2.
- 14.7 Cladding materials must comply with the fire performance requirements of NZBC Acceptable Solution C/AS1 or C/AS2 based on the building height, distance of the external wall to the relevant boundary and if the building is sprinklered. The Insulated Façade System has not been assessed for use where these requirements apply.

External Moisture

- 15.1 Insulated Façade System, when installed in accordance with this Appraisal and the Technical Literature, prevents the penetration of moisture that could cause undue dampness or damage to building elements.
- 15.2 The cavity must be sealed off from the roof and subfloor space to meet code compliance with NZBC Clause E2.3.5.
- 15.3 Insulated Façade System allows excess moisture present at the completion of construction to be dissipated without permanent damage to building elements to meet code compliance with NZBC Clause E2.3.6.
- 15.4 The details given in the Technical Literature for weather sealing are based on the design principle of having a first and second line of defence against moisture entry for all joints, penetrations and junctions. The ingress of moisture must be excluded by detailing joinery and wall interfaces as shown in the Technical Literature. Weathertightness details that are developed by the designer are outside the scope of this Appraisal and are the responsibility of the designer for compliance with the NZBC.

- 15.5 The use of Insulated Façade System where there is a designed cavity drainage path for moisture that penetrates the cladding, does not reduce the requirement for junctions, penetrations, etc. to remain weather-resistant.

Internal Moisture

- 16.1 Insulated Façade System alone does not meet NZBC Acceptable Solution E3/AS1. Buildings must be constructed with an adequate combination of thermal resistance and ventilation, and space temperature must be provided to all habitable spaces, bathrooms, laundries and other spaces where moisture may be generated or may accumulate.

Water Vapour

- 16.2 Insulated Façade System is not a barrier to the passage of water vapour, and when correctly installed will not create or increase the risk of moisture damage resulting from condensation.
- 16.3 When Insulated Façade System is installed over a steel frame, the battens and insulated drainage cavity will act as a thermal break to the steel frame in accordance with NZBC Acceptable Solution E3/AS1.

Installation Information

Installation Skill Level Requirement

- 17.1 Installation and finishing of components and accessories supplied by Resene Construction Systems and its approved installers must be completed by trained installers, approved by Resene Construction Systems.
- 17.2 Installation of the accessories supplied by the building contractor must be carried out in accordance with Insulated Façade System Technical Literature and this Appraisal by, or under the supervision of, a Licensed Building Practitioner [LBP] with the relevant License Class.

System Installation

Wall Underlay and Flexible Sill and Jamb Tape Installation

- 18.1 The selected wall underlay and flexible sill and jamb tape system must be installed by the building contractor in accordance with the underlay and tape manufacturer's instructions prior to the installation of the cavity battens and the rest of Insulated Façade System. Flexible wall underlay must be installed horizontally and be continuous around corners. Underlay must be lapped 75 mm minimum at horizontal joints and 150 mm minimum over studs at vertical joints. Generic rigid wall underlay materials must be installed in accordance with NZBC Acceptable Solution E2/AS1 and be overlaid with a flexible wall underlay. Proprietary systems shall be installed in accordance with the manufacturer's instructions. Particular attention must be paid to the installation of the wall underlay and sill and jamb tapes around window and door openings to ensure a continuous seal is achieved and all exposed wall framing in the opening is protected.
- 18.2 Where studs are at greater than 450 mm centres and a flexible wall underlay is being used, a wall underlay support must be installed over the underlay at maximum 300 mm centres horizontally.

Aluminium Joinery Installation

- 18.3 Aluminium joinery and associated head flashings must be installed by the building contractor in accordance with the Technical Literature. A 7.5-10 mm nominal gap must be left between the joinery reveal and the wall framing so a PEF rod and air seal can be installed after the joinery has been secured in place.

Insulated Façade System

- 18.4 The system must be installed in accordance with the Technical Literature by Resene Construction Systems approved installers.
- 18.5 The plaster system must only be applied when the air and substrate temperature is within the range of 5-30°C.

Inspections

- 18.6 The Technical Literature must be referred to during the inspection of Insulated Façade System installations.

Finishing

- 18.7 The paint manufacturers' instructions must be followed at all times for application of the paint finish. The plaster must be cured for a minimum of 2-3 days and must be dry before commencing painting.

Health and Safety

- 19.1 Safe use and handling procedures for the components that make up Insulated Façade System are provided in the relevant manufacturer's Technical Literature.

Basis of Appraisal

The following is a summary of the technical investigations carried out:

Tests

- 20.1 The following testing has been completed by BRANZ:
- BRANZ expert opinion on NZBC Clause E2 code compliance for Insulated Façade System was based on evaluation of all details within the scope and as stated within this Appraisal and testing of the Resene Construction Systems Insulated Facade System to NZBC E2/VM1. The testing assessed the performance of the foundation detail, window head, jamb and sill details, meter box head, jamb and sill details, vertical and horizontal control joints, internal and external corners and balustrade to wall junction with a plastered cap. In addition to the weathertightness test, the details contained within the Technical Literature have been reviewed, and an opinion has been given by BRANZ technical experts that the system will meet the performance levels of NZBC Acceptable Solution E2/AS1 for drained cavity claddings.
 - Wind face load and fastener pull through testing for EIFS cladding systems. BRANZ determined design wind suction pressures, and by comparing these pressures with AS/NZS 1170 pressure coefficients, the fixing requirements were determined for timber and steel-framed walls.
 - The Insulated Façade System comprising Graphex or XTherm Gold [PIR] sheet, mineral base coat, mineral texture, Resene Limelock and Resene Lumbersider or X200 painted finish has been tested in accordance with ISO 5660 and achieved a Type A classification. Testing was carried out as per the NZBC Building Product Specifications.
 - The Insulated Façade System comprising EPS sheet, mineral base coat with mineral texture finish, Resene Limelock, and Resene Lumbersider or X200 painted finish coat has been tested in accordance with ISO 5660 and achieved a Type B classification. Testing was carried out as per the NZBC Building Product Specifications.

Other Investigations

- 21.1 Structural and durability opinions have been given by BRANZ technical experts.
- 21.2 Site inspections have been carried out by BRANZ to assess the practicability of installation, and to examine completed installations.
- 21.3 The manufacturer's Technical Literature has been examined by BRANZ and found to be satisfactory.

Quality

- 22.1 The manufacture of the plasters and finishes has been examined by BRANZ, including methods adopted for quality control. Details regarding the quality and composition of the materials used were obtained by BRANZ and found to be satisfactory.
- 22.2 The quality of materials, components and accessories supplied by Resene Construction Systems is the responsibility of Resene Construction Systems.
- 22.3 Quality on-site is the responsibility of the Resene Construction Systems approved installers.



- 22.4 Designers are responsible for the building design, and building contractors are responsible for the quality of installation of framing systems and joinery, wall underlays, flashing tapes, air seals and joinery head flashings in accordance with the instructions of Resene Construction Systems.
- 22.5 Building owners are responsible for the maintenance of Insulated Façade System in accordance with the instructions of Resene Construction Systems.

Sources of Information

- AS 1366.3:1992 Rigid cellular plastic sheets for thermal insulation - Rigid cellular polystyrene - Moulded [RC/PS-M]
- AS 3566:2002 Self-drilling screws for the building and construction industries.
- AS/NZS 1170:2002 Structural design action – General principles.
- ISO 5660.1:2002 Reaction-to-fire tests - Heat release, smoke production and mass loss rate [cone calorimeter method].
- NZS 3602:2003 Timber and wood-based products for use in building.
- NZS 3603:1993 Timber structures standard.
- NZS 3604:2011 Timber-framed buildings.
- NZS 4211:2008 Specification for performance of windows.
- NZS 4214:2006 Methods of determining the total thermal resistance of parts of buildings.
- Ministry of Business, Innovation and Employment Record of amendments - Acceptable Solutions, Verification Methods and handbooks.
- The Building Regulations 1992.

Amendments

Amendment No. 1, dated 10 June 2026

This Appraisal has been amended to remove the requirement for a control joint at 6 m intervals and to reflect the changes made to the NZBC compliance documentation.



BRANZ Appraised
Appraisal No. 633 [2024]

BRANZ Appraisal
Appraisal No. 633 [2024]
06 September 2024

INSULATED FAÇADE SYSTEM



In the opinion of BRANZ, the **Insulated Façade System** is fit for purpose and will comply with the Building Code to the extent specified in this Appraisal provided it is used, designed, installed and maintained as set out in this Appraisal.

The Appraisal is issued only to **Rockcote Resene Ltd T/A Resene Construction Systems**, and is valid until further notice, subject to the Conditions of Appraisal.

Conditions of Appraisal

1. This Appraisal:
 - a) relates only to the product as described herein;
 - b) must be read, considered and used in full together with the Technical Literature;
 - c) does not address any Legislation, Regulations, Codes or Standards, not specifically named herein;
 - d) is copyright of BRANZ.
2. **Rockcote Resene Ltd T/A Resene Construction Systems**:
 - a) continues to have the product reviewed by BRANZ;
 - b) shall notify BRANZ of any changes in product specification or quality assurance measures prior to the product being marketed;
 - c) abides by the BRANZ Appraisals Services Terms and Conditions;
 - d) warrants that the product and the manufacturing process for the product are maintained at or above the standards, levels and quality assessed and found satisfactory by BRANZ pursuant to BRANZ's Appraisal of the product.
3. BRANZ makes no representation or warranty as to:
 - a) the nature of individual examples of, batches of, or individual installations of the product, including methods and quality of work;
 - b) the presence or absence of any patent or similar rights subsisting in the product or any other product;
 - c) any guarantee or warranty offered by **Rockcote Resene Ltd T/A Resene Construction Systems**.
4. Any reference in this Appraisal to any other publication shall be read as a reference to the version of the publication specified in this Appraisal.
5. BRANZ provides no certification, guarantee, indemnity or warranty, to **Rockcote Resene Ltd T/A Resene Construction Systems** or any third party.

For BRANZ

Claire Falck

Chief Executive

Date of Issue:

06 September 2024